



NOTES:

1. ALL WORK SHOWN ON THIS PLAN IS TYPE B.

WATER APPURTENANCES ADJUSTMENT & RELOCATION FOR BULBOUT CONSTRUCTION			
NO.	DESCRIPTION	NORTHING	EASTING
①	ABANDON (E) 8" DIV VALVE; REMOVE BOX & COVER	2105192.9520	5990296.5650
②	REMOVE (E) LPFH	2105199.5740	5990307.4770
③	ABANDON (E) LPFH VALVE; REMOVE BOX & COVER	2105195.8660	5990307.6360
④	RELOCATE (E) WATER METER	2105238.5372	5990290.5596

FOR THE SOLE USE OF THE DOCUMENT RECIPIENT
- DO NOT CITE, COPY, OR CIRCULATE WITHOUT
THE EXPRESSED PERMISSION OF THE SFPUC.

REFERENCES
GATE BOOK PAGES, PLANS,
SURVEY NOTES, ETC., USED

54 & 70

CCSF 2013
NAVD88



2-4-2020

NO.	DATE	DESCRIPTION	BY	APPR'D
1	01/22/20	ADDENDUM 1 - PIPELINE REVISED	RS	RT

WATER CONTRACT NO. WD-2775 CONTRACT NO. 2652J		
CITY AND COUNTY OF SAN FRANCISCO PUBLIC UTILITIES COMMISSION INFRASTRUCTURE DIVISION ENGINEERING MANAGEMENT BUREAU		
INSTALLATION OF 16-INCH AND 36-INCH, AND RELOCATION OF 8-INCH DUCTILE IRON WATER MAINS AT VARIOUS LOCATIONS ON 19TH AVENUE FROM HOLLOWAY AVENUE TO LINCOLN WAY WATER APPURTENANCES TO ADJUST OR RELOCATE AT KIRKHAM ST NE		
CHECKED / APPROVED	DRAWN	AS SHOWN
SECTION MANAGER	DESIGNED	OCT 2018
APPROVED	APPROVED	
MANAGER, ENGINEERING MANAGEMENT BUREAU		MANAGER, CITY DISTRIBUTION DIVISION
SHEET	PLAN NO.	REVISION NO.
OF	WD-2775-27B	E-31410

