


TYPICAL TRENCH FOR AWSS PIPE IN NON-CALTRANS RIGHT-OF-WAY

NOTES

- 1. MINIMUM TRENCH DEPTHS AND TRENCH WIDTHS MUST BE ADHERED TO UNLESS OTHERWISE APPROVED BY THE CITY REPRESENTATIVE.
- 2. OVER EXCAVATION FOR BEDDING IS NOT REQUIRED UNLESS:
- A. BOTTOM OF TRENCH EXCAVATION IS IN BEDROCK, WHERE BEDDING SHALL BE 12" THICK.
- B. BEDDING SHALL BE APPROVED CLEAN SAND OR 3/4" DRAIN ROCK. SAND SHALL BE COMPACTED TO 95% RELATIVE COMPACTION.
- 3. WARNING TAPE SHALL BE 6" WIDE, YELLOW COLORED NON-DETECTABLE TYPE. INSCRIPTION MESSAGE, USING 1.5" MINIMUM HEIGHT BLACK TEXT, SPACED AT 3'-0" FT MAXIMUM INTERVALS, SHALL READ "CAUTION - SFFD AWSS WATER PIPELINE BELOW". WARNING TAPE SHALL OVERLAP 12" MINIMUM AT SPLICES.
- 4. TRENCH CONSTRUCTION SHALL CONFORM TO OSHA AND CAL OSHA REGULATIONS.
- 5. 12" DI AWSS PIPE SHOWN WITH STOP COLLAR IN PLACE. 6" MINIMUM DIMENSION IS FROM BOTTOMMOST PAIR OF LUGS TO BOTTOM OF TRENCH.
- 6. AREAS UNDER THE ADDITIONAL 1' PAVEMENT AND CONCRETE ROAD BASE TO BE REMOVED FOR THE T-TRENCH RESTORATION SHALL BE SCARIFIED, RESHAPED, AND COMPACTED TO THE REQUIRED DENSITY PRIOR TO FURTHER CONSTRUCTION.
- 7. REFER TO SPEC SECTION 31 22 33 CONTROLLED LOW STRENGTH MATERIAL FOR CALTRANS' REQUIRED SLURRY CEMENT.
- 8. TACK COAT (ASPHALTIC EMULSION) SHALL BE APPLIED TO PRIOR TO PLACING HMA-A

FOR THE SOLE USE OF THE DOCUMENT RECIPIENT - DO NOT CITE, COPY, OR CIRCULATE WITHOUT THE EXPRESS PERMISSION OF THE SFPUC.

PLAN APPROVAL DATE PROJECT ID CONTRACT No. DISTRICT COUNTY POST MILES TOTAL PROJECT ROUTE 04-0G3501 0400000325 R0.94/4.05



TYPICAL TRENCH FOR AWSS PIPE IN CALTRANS RIGHT-OF-WAY

NOMINAL AWSS PIPE DIAMETER (PIPE SLEEVING)	MINIMUM TRENCH WIDTH "A"
8"	36"
10", 12"	42"
14", 16"	48"
18", 20"	60"
(24")	72"
(30", 32")	80"
(36", 42")	90"

CITY AND COUNTY OF SAN FRANCISCO SAN FRANCISCO PUBLIC WORKS BUREAU OF DESIGN AND ENGINEERING

CITY AND COUNTY OF SAN FRANCISCO PUBLIC UTILITIES COMMISSION WATER ENTERPRISE CITY DISTRIBUTION DIVISION

19TH AVENUE (STATE ROUTE 1)
COMBINED CITY PROJECT

Eugents 12/11/18 DRAWN MM/WC 01/2019 AUXILIARY WATER SUPPLY SYSTEM WORK THOUSE IN/18/18 DESIGNED MBS 01/2019 DETAILS I

BURBAL HANAGER 12/24/18 CHECKED EL 01/201 NONE 01/2019 NO. DATE DESCRIPTION BY APPR'C 284 OF 356 MA-D07 111,582 REVISIONS

REFERENCES GATE BOOK PAGES, PLANS, SURVEY NOTES, ETC, USED

GATE BOOK PAGES No. M 30683 Exp. 06/30/20

OF CALIF